

Technical Service Bulletin


Date: April 12, 2021

Subject: SD-670DE Firmware Updating

Issue: General Instructions on updating the firmware for SD-670DE. Please contact Maxon Technical Department 800-456-2071 for detailed information on each firmware release.

Instructions:

1. Unzip the firmware release you wish to use. If you have .BIN files for your firmware update, you can move them to the DataFile folder for the SD-670DE programmer for it to find easily later.




2. Read the radio using the programmer and click on the Download tab.




3. Select the serial port number and open the VHF or UHF file that is the firmware version you wish to update to.

 SD671D_MAXON_V1010.bin	10/25/2019 11:02 AM	Radio Data Files	151 KB
 SD674D_MAXON_V1010.bin	10/25/2019 11:02 AM	Radio Data Files	151 KB



4. Move the selector switch on the programming cable to “DL”.
5. Plug the DE15 end of the programming cable into the radio. The LED on the radio should not illuminate.
6. Click on the “Write Firmware” button. Do not remove the radio until it is 100% complete or damage will occur to the radio.



Repeat the steps if there are any issues during programming. You can also call our number and ask for Tech Support.